

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Quotation Notice

Item rates sealed quotations are invited from approved and eligible contractors of C.P.WD/U.P.PW.D./M.E.S./Railways/Contractors registered in Central/State public undertakings for the work of "Dismantling and repairing of divider in front of gate of Ambedkar Bhawan" with an Estimated cost of Rs. 34,630.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by Speed Post only, addressed to, "Deputy Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025" in the University up to 3:00 P.M till 03.05.2018

The quotations are available on the website of the University only and may be downloaded from bbau.ac.in Time of opening of quotations to be displayed on the website of University.

Conditions:-

- 1- The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
- 2- Work should be carried out as per all edition of C.P.W.D. specifications.
- 3- All material required for completion of work shall conform to latest ISI/CPWD specifications.
- 4- Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
- 5- Time of completion shall be **15 Days** from the date of issue of the work order.
- 6- Income Tax/ Trade tax shall be deducted as per rule of Government of India/ State Government.
- 7- Photocopies of registration in Income tax/ Trade tax department should be submitted alongwith the quotation.
- 8- Rates quoted shall be valid at least for three months from the date of opening of the quotations.
- 9- University has the right to reject and one or all quotations without assigning any reason.


Finance Officer
19.4.18

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Letter No. 202/5(499)/2018

Dated:- 19/04/2018

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action (**Internal circulation through E-mail only**):-

- 1- S.O. to V.C's, BBAU, Lucknow.
- 2- D.R. (S&P), BBAU, Lucknow for doing the needful.
- 3- In-charge website with a request to upload it on the website of the University.


Finance Officer

B.O.Q

Name of work: Dismantling and repairing of divider in front of gate of Ambedkar Bhawan.

S. No	Item	Qty	Unit	Rate
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar.	3.45	Cum	
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	11.47	Cum	
3	Scrapping the speed breakr making good the same including supply of extra quantities of materials i.e. aggregate, moorum screening, red bajri and labour required. bituminous portion.	0.47	Cum	
4	Surface dressing on old surface with hot bitumen of grade VG - 10 of approved quality using 1.95 kg of bitumen per sqm with 1.50 cum of stone chippings 11.2 mm nominal size per 100 sqm of road surface, including consolidation with road roller of 6 to 8 tonne capacity, etc. complete.	24.00	Sqm	
5	Providing and applying tack coat using hot straight run bitumen of grade VG - 10, including heating the bitumen, spraying the bitumen with mechanically operated spray unit fitted on bitumen boiler, cleaning and preparing the existing road surface as per specifications :	11.20	Sqm	
6	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Batch Type Hot Mix Plant of 100-120 TPH capacity.	2.77	Cum	
7	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	0.46	Cum	
8	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia nominal bore	15.00	Mtr	
9	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	9.38	Sqm	
10	Painting runway/taxi track/apron marking with adequate nos of coats to give uniform finish with road marking paint of superior make as approved by the Engineer-in-charge, i/c cleaning the surface of ail dirt, scales, oil, grease and other foreign mater;al etc. and lining out complete. New work (Two or more coats).	9.38	Sqm	
Total Amounts in figure				
Total Amounts in words				

Name of Bidder with signature and seal.....