

# BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

## Quotation Notice

Item rates sealed quotations are invited from approved and eligible contractors of C.P.WD/U.P.PW.D./M.E.S./Railways/Contractors registered in Central/State public undertakings for the work of "Construction of interlocking paver block pathway at parking entrance of Central Library near Guest House T-Junction." with an Estimated cost of Rs. 55,811.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by Speed Post only, addressed to, "Deputy Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025" in the University up to 3:00 P.M till 17.07.2018.

The quotations are available on the website of the University only and may be downloaded from [bbau.ac.in](http://bbau.ac.in) Time of opening of quotations to be displayed on the website of University.

### Conditions:-

- 1- The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
- 2- Work should be carried out as per all edition of C.P.W.D. specifications.
- 3- All material required for completion of work shall conform to latest ISI/CPWD specifications.
- 4- Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
- 5- Time of completion shall be **15 Days** from the date of issue of the work order.
- 6- Income Tax/ Trade tax shall be deducted as per rule of Government of India/ State Government.
- 7- Photocopies of registration in Income tax/ Trade tax department should be submitted alongwith the quotation.
- 8- Rates quoted shall be valid at least for three months from the date of opening of the quotations.
- 9- University has the right to reject and one or all quotations without assigning any reason.

  
Registrar

# BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

Letter No. 226/5(580)/2018 Part-3

Dated:- 4/07/2018

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action (*Internal circulation through E-mail only*):-

- 1- S.O. Finance Officer, BBAU, Lucknow.
- 2- D.R. (S&P), BBAU, Lucknow for doing the needful.
- 3- In-charge website with a request to upload it on the website of the University.

  
Registrar

## B.O.Q

**Name of work:** Construction of interlocking paver block pathway at parking entrance of Central Library near Guest House T-junction.

S. No	Item	Unit	Qty	Rate	Amount in Rs.
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil	Sqm	46.00		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil.	Cum	1.70		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III); 10 graded stone aggregate 40 mm nominal	Cum	1.82		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	Cum	2.55		
5	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand).	Sqm	27.79		
6	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	Sqm	27.68		
7	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	46.00		
	<b>Total Amounts in figure</b>				
	<b>Total Amounts in words</b>				