

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

Quotation Notice

Item rates sealed quotation are invited from approved and eligible contractors of C.P.WD/U.P.P.W.D./M.E.S./Railways/CPSUs/SPSUs for the following work of "Repairing of damaged granite4 stone & floor tile of Chitrlekha Girls Hostel" with an Estimated cost of Rs. 75,655.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by Speed Post only, addressed to, "Deputy Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025" in the University up to 3:00 P.M till 26.07.2018.

The quotations are available on the website of the University only and may be downloaded from bbau.ac.in Time of opening of quotations to be displayed on the website of University.

Conditions:-

1. The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. specifications.
3. All material required for completion of work shall conform to latest ISI/CPWD specifications.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be **15 Days** from the date of issue of the work order.
6. Income Tax/ Trade tax shall be deducted as per rule of Government of India/ State Government.
7. Photocopies of registration in Income tax/ Trade tax department should be submitted alongwith the quotation.
8. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
9. University has the right to reject and one or all quotations without assigning any reason.

Registrar

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

Letter No. 229/EE/5(477)/2018

Dated:- 12/07/2018

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action (*Internal circulation through E-mail only*):-

1. S.O. to V.C.'s, BBAU, Lucknow.
2. Finance Officer, BBAU, Lucknow.
3. D.R. (S&P), BBAU, Lucknow for doing the needful.
4. Warden Chitrlekha Girls Hostel, BBAU, Lucknow.
5. In-charge website with a request to upload it on the website of the University

Registrar

B.O.Q

Name of work:- Repairing of damaged granite stone & floor tiles of Chitrlekha Girls Hostel.

S. No	Item	Qty	Unit	Rate	Amount in Rs.
1	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	12.25	Sqm		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm.	16.74	Sqm		
3	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Area of slab over 0.50 sqm.	12.25	Sqm		
4	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	16.74	Sqm		
5	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1 cement: 4 coarse sand).	5.25	Sqm		
6	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm).	5.25	Sqm		
	Total Amounts in figure				
	Total Amounts in words				

Name of Bidder with signature and seal.....