

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Quotation Notice

Item rates sealed quotations are invited from approved and eligible contractors of C.P.WD/U.P.P.W.D./M.E.S./Railways/CPSUs/SPSUs for the following work of “**Construction of M.S. Grill on opening and security wall to prevent the entry of dogs into Ashoka Boys Hostel Building**” with an **Estimated cost of Rs. 56,588.00** B.O.Q. of work as per Annexure-I. The quotations shall be received by **Speed Post** only, addressed to, “**Deputy Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025**” in the University up to 3:00 P.M till **15.05.2019**.

The quotations are available on the website of the University only and may be downloaded from bbau.ac.in Time of opening of quotations to be displayed on the website of University.

Conditions:-

1. The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. specifications.
3. All material required for completion of work shall conform to latest ISI/CPWD specifications.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be **01 Month** after 10 days from the date of issue of the work order.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/ State Government.
7. Photocopies of registration in Income tax/ Trade tax department should be submitted alongwith the quotation.
8. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
9. University has the right to reject and one or all quotations without assigning any reason.


Registrar

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Letter No. **305/EE** /5(624)/2019

Dated:- **08/5/19**

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action.

1. S.O. to V.C.'s, BBAU, Lucknow.
2. Warden, Ashoka Boys Hostel BBAU, Lucknow.
3. D.R. (S&P), BBAU, Lucknow for doing the needful.
4. In-charge website with a request to upload it on the website of the University.


Registrar

B.O.Q

Name of work: Construction of M.S. Grill on opening and security wall to prevent the entrance of dogs into Ahoska Boys Hostel Building.

S. No	Item	Unit	Qty	Rate	Amount
1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m : All kinds of soil.	Cum	0.64		
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing : 1:5:10 (1 cement : 5 coarse sand (zone-III) : 10 graded stone aggregate 40 mm nominal size).	Cum	0.13		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 coarse sand).	Cum	0.33		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	3.35		
5	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand).	Sqm	30.22		
6	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm).	Sqm	30.22		
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	Kg	268.84		
8	Providing and fixing carbon steel galvanised (minimum coating 5 micron) dash fastener of 10 mm dia double threaded 6.8 grade (yield strength 480 N/mm ²), counter sunk head, comprising of 10 m dia polyamide PA 6 grade sleeve, including drilling of hole in frame , concrete/ masonry, etc. as per direction of Engineer-in-charge. 10 x 80 mm.	Each	36.00		
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	Sqm	17.13		
Total Amounts in figure					
Total Amounts in words					

Name of Bidder with signature and seal.....