

**BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY**  
**University Works Department**

**Extension of Quotation Notice**

Letter no. 417/BBAU/ 5/(196)/2019 Part-5

Dated : 29/5/19

The last date of the submission of the quotation invited vide letter no. 310/EE/5(196)/2019 Part-5 dated 16.05.2019 for the work of "**Construction of water disposal 150 mm Dia PVC pipe channel with chamber at V.C. Residence**" is hereby extended up to 3:00 P.M. on **10.06.2019**. The quotation shall be opened at 3:30 P.M. on the same day:-

Rest of the conditions will remain same.

Registrar

Copy forwarded to the following for information and necessary action (*Internal circulation through E-mail only*).

1. S.O. V.C's Secretariat, BBAU, Lucknow.
2. Deputy Registrar (S&P), BBAU, Lucknow, for doing the needful.
3. In-charge website for uploading, Tender notice & Tender document complete, BBAU, Lucknow.

  
Registrar

**B.O.Q**

Name of work: Construction of water disposal 150 mm Dia PVC pipe channel with chamber at V.C. Residence.

S. No	Item	Qty	Unit	Rate	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil.	3.28	Sqm	500.00	1,640.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size).	0.60	Sqm	5000.00	3,000.00
3	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 150 mm nominal size dia.	22.00	Mtr.		
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	0.45	Cum		
5	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand).	2.06	Sqm		
6	Providing and fixing at or near ground level precast cement concrete in kerbs, edgings etc. as per approved pattern and setting in position with cement mortar 1:3 (1 Cement : 3 coarse sand), including the cost of required centering, shuttering complete. 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal	0.06	Cum		
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	4.55	Kg		
8	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix).	0.20	Cum		
9	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	0.29	Cum		
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	3.12	Cum		
<b>Total Amounts in figure</b>					
<b>Total Amounts in words</b>					

Name of Bidder with signature and seal.....