

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

60

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Quotation Notice

Item wise rates of sealed Quotations are invited from approved and eligible contractors of C.P.WD/U.P.P.W.D./M.E.S./Railways/CPSUs/SPSUs for the following work of "Repairing and Maintenance of External Damaged plaster and settled plinth protection and cracks surrounding building of Central Library" with an Estimated cost of Rs. 47,157.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by Speed Post only, addressed to, "Assistant Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025" in the University up to 3.00 P.M till 03.06.2020

The quotations are available on the website of the University only and may be downloaded from bbau.ac.in Time of opening of quotations to be displayed on the website of University.

Conditions:-

1. The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
2. Work should be carried out as per all edition of C.P.W.D. specifications.
3. All material required for completion of work shall conform to latest ISI/CPWD specifications.
4. Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5. Time of completion shall be 30 Days.
6. Income Tax/GST tax shall be deducted as per rule of Government of India/ State Government.
7. Photocopies of registration in Income tax/ Trade tax department should be submitted along with the quotation.
8. Rates quoted shall be valid at least for three months from the date of opening of the quotations.
9. University has the right to reject and one or all quotations without assigning any reason.

Registrar

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY

VIDYA VIHAR RAEBARAELI ROAD, LUCKNOW

Letter No. 377/EB/5(580)/2020 Part-3

Dated:- 18/05/2020

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action.

1. S.O. to V.C.'s Secretariat, BBAU, Lucknow.
2. A.R. (S&P), BBAU, Lucknow for doing the needful.
3. In-charge website with a request to upload it on the website of the University.

Registrar

B.O.Q

Name of work: Repairing and Maintenance of External Damaged plaster and settled plinth protection and cracks surrounding building of Central Library.

S. No	DSR Code	Item	Unit	Qty	Rate	Amount
1	15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	Cum	2.19		
2	2.2.1	Earth work in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and lift upto 1.5 m : All kinds of soil.	Cum	18.00		
3	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size).	Cum	1.46		
4	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size).	Cum	1.96		
5	14.1.2	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 coarse sand).	Sqm	7.65		
6	13.47.1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm).	Sqm	7.65		
7	14.17	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or replastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	Sqm	40.83		
8	8.2.2.1	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble, Granite of any colour and shade Area of slab upto 0.50 sqm.	Sqm	0.34		
9	11.50	Deduct for not grouting the joints with white cement and matching pigment in the items of fixing of vitrified tiles.	Sqm	1.24		
Total Amounts in figure						
Total Amounts in words						

Name of Bidder with signature and seal.....