

(7)

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY
VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

Quotation Notice

Item rates sealed quotations are invited from approved and eligible contractors of C.P.WD/U.P.PW.D./M.E.S./Railways/Contractors registered in Central/State public undertakings for the work of "Providing and fixing of ACP sheet at front side of Auditorium stage" with an Estimated cost of Rs. 84,395.00 B.O.Q. of work as per Annexure-1. The quotations shall be received by Speed Post only, addressed to, "Assistant Registrar (Store & Purchase), Babasaheb Bhimrao Ambedkar, Lucknow-226025" in the University up to 3:00 P.M till05.12.2017).

The quotations are available on the website of the University only and may be downloaded from bbau.ac.in Time of opening of quotations to be displayed on the website of University.

Conditions:-

- 1- The rates quoted should be included the rates for all materials, labours, T&P, cartage, taxes, etc. required for proper completion of work.
- 2- Work should be carried out as per all edition of C.P.W.D. specifications.
- 3- All material required for completion of work shall conform to latest ISI/CPWD specifications.
- 4- Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
- 5- Time of completion shall be **01 Week** from the date of issue of the work order.
- 6- Income Tax/ Trade tax shall be deducted as per rule of Government of India/ State Government.
- 7- Photocopies of registration in Income tax/ Trade tax department should be submitted along with the quotation.
- 8- Letter sent at the address given by the contractor shall be deemed to have been received by the contractor.
- 9- Rates quoted shall be valid at least for three months from the date of opening of the quotations.
- 10- University has the right to reject and one or all quotations without assigning any reason.

Finance Officer

BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY
VIDYA VIHAR RAEBARAEI ROAD, LUCKNOW

Letter No. 1781 — /EO/BBAU/120/2017

Dated:- 29-11-2017

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action (**Internal circulation through E-mail only**):-

- 1- S.O. to V.C's, BBAU, Lucknow.
- 2- S.O. Finance Officer, BBAU, Lucknow.
- 3- A.R. (S&P), BBAU, Lucknow for doing the needful.
- 4- Estate Officer, BBAU, Lucknow.
- 5- In-charge website with a request to upload it on the website of the University.

Finance Officer



B.O.Q

Work: Providing and fixing of ACP sheet at front side of Auditorium stage.

No	Item	Qty	Unit	Rate	Amount (Rs.)
1	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 meters lead as directed by Engineer-in-charge.	24.36	Sqm		
2	<p>Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building , for all heights and all levels etc. including:</p> <p>a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design.</p> <p>(b) Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc.</p> <p>(c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316, Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel cladding, cleaning and protection of the curtain wall with aluminium composite panel cladding till the handing over of the building for occupation. Base frame work for ACP cladding is payable under the relevant aluminium items The Contractor shall provide curtain wall with aluminium composite panel cladding, having all the performance characteristics all complete , as per the Architectural drawings, as per item description, as specified, as per the approved shop drawings and as directed by the Engineer-in-Charge. However, for the purpose of payment, only the actual area on the external face of the curtain wall with Aluminum Composite Panel Cladding (including width of groove) shall be measured in sqm. up to two decimal places."</p>	24.36	Sqm		
	Total Amounts in figure				
	Total Amounts in words				

Name of Bidder with signature and seal.....