BABASAHEB BHIMRAO AMBEDKAR UNIVERSITY
LUCKNOW
प्रज्ञा शील करुणा
ESTABLISHED 1996

बाबासाहेब भीमराव अम्बेडकर विश्वविद्यालय
विद्या विहार, रायबरेली रोड, लखनऊ–226025
Babasaheb Bhimrao Ambedkar University
(A Central University)
Vidya Vihar, Raebareli Road, Lucknow-226025

Letter No. : ENG/4627/-L Date : 13/08/2026

QUOTATION NOTICE

Sealed Quotations are re-invited from approved and eligible contractors of BBAU/C.P.W.D. /U.P.PW.D./M.E.S./Railways or Contractors registered in Central/State public undertakings for the work of **"Supply, Installation and Commissioning of Sound System in the Conference Hall of the Old Administrative Building at BBAU Campus, Lucknow."** The **Estimated cost of work is Rs. 2,42,100.00** as per the details given in B.O.Q. **(Annexure-1).**

The quotations shall be received by **Speed Post/Registered Post** only to **Registrar, Babasaheb Bhimrao Ambedkar, Lucknow-226025** clearly written "Quotation/Tenders for the work of **"Supply, Installation and Commissioning of Sound System in the Conference Hall of the Old Administrative Building at BBAU Campus, Lucknow."** in the University up to 3:00 P.M. till 20/8/26 By hand Quotations/Tenders will not be accepted by the University under any circumstances.

Terms & Conditions:-

1- The rates quoted should include the rates for all materials, cartage, taxes, etc. required for proper completion of work.
2- Work should be carried out as per detailed C.P.W.D. specifications.
3- All material required for completion of work shall conform to latest ISI/CPWD specifications.
4- Payment shall be released after completion of work to the satisfaction of Engineer-in-charge.
5- Time of completion shall be **45 days** from the date of issue of order.
6- Income Tax shall be deducted as per rule of Government of India/ State Government.
7- Photocopies of registration on Income Tax/ GST department should be submitted along with the quotation.
8- Rates quoted shall be valid at least for **Six Months** from the date of opening of the quotations.
9- University has the right to reject and one or all quotations without assigning any reason.

14/8/26
Registrar

Copy forwarded to the following along with the copy of Annexure-1 for information and necessary action ***(Internal circulation through E-mail only):-***

1- Section Officer, Vice-Chancellor Secretariat, BBAU, Lucknow.
2- Assistant Registrar (S&P), BBAU, Lucknow for doing the needful.
3- In-charge website with a request to upload it on the website of the University.

Executive Engineer

Annexure – 1

Name of work - Supply, Installation and Commissioning of Sound System in the Conference Hall of the Old Administrative Building at BBAU Campus, Lucknow.

S.No.	Description of the Item	Unit	Quantity	Rate	Amount
1	Ahuja Compact superior quality speaker system comprising of a single 12" Full Range Dual Cone speaker and a Piezo Horn Tweeter. The system is outstanding for its ability to handle 100W continuous power with undistorted response and is ideal for small PA applications. The speakers are housed in a Rugged Closed box Enclosure made of 18mm board, and Carpet covered.	Pcs	2	32,500.00	65,000.00
2	Ahuja Ceiling Speaker High quality flush mount ceiling speaker with stylish grill and frame, which integrate wonderfully well with all interiors. Clear and clean sound for speech and music. 8" Dual Cone Full Range Speaker, 15W/100V. High fidelity and excellent frequency response. 100V line operation with easy power tap selection through a terminal block. Superbly engineered for simple and safe installations. Ideal for Offices... Restaurants... Hotel... Hospitals... Shopping Malls... Gymnasiums..	Pcs	12	3,250.00	39,000.00
3	Ahuja 12-Channel Input Channels: Each Channel has separate 1/4" balanced phone jack for Mic and Line & accepts both balanced & unbalanced signals. AUX Control: This controls the level of the channel in the final mix to Aux Send output. AUX Send & AUX Return: These have been provided for sending the pre-fader output of channels for monitoring or for adding a Special Effects Unit. MONO/STEREO Output: Mono output is available from either Left & Right output jacks when the switch is in 'Mono' position. Each channel has GAIN, BASS, MID, TREBLE, ECHO, PAN and slide LEVEL controls with CLIP LED indicator. Echo section provided with Delay, Repeat & Level controls. Tape section for Record & Playback facility.	Pcs	1	35,000.00	35,000.00
4	Ahuja It is a permanently fixed model. In addition, the monitor fixing area can be rotated left and right. Universal Vesa Mounting To Fixed any Type of Patients Monitor MS Epoxy powder coating. Basket to hold the cables of the monitor to Hold Monitor accessories like BP CUFF and Probes Tray Dimensions: Universal Vesa Mounting To Fixed any Type of Patients Monitor | Basket Dimensions: 24 x 15 x 14 CMS	Pcs	2	3,800.00	7,600.00
5	Ahuja Speaker wire ensures signal clarity and minimal distortion or signal loss even for longer distances. It helps in connecting loudspeakers and audio amplifiers smoothly.	Roll	3	9,000.00	27,000.00
6	Ahuja Podium Microphone Stylish and rugged high band VHF wireless desktop microphone & receiver available in different frequencies. Single zone desktop paging microphone with a sturdy, aluminium die-cast top and special high reliability switches with integrated LED indicators. Fitted with a flexible 300mm (12") gooseneck and a high quality unidirectional dynamic cartridge. Supplied with 6 mtrs. twin core shielded low noise cable with 6.3mm (4") phone plug.	Pcs	2	12,500.00	25,000.00
7	Ahuja Compact, lightweight, Dual Channel VHF Wireless Microphone System. Operates at Quartz Crystal Locked VHF High Band frequency and available in different frequency groups. Two transmitters with separate frequencies and one dual channel receiver. Internal antenna in the transmitter and two telescopic antennas in the receiver for clear and distortion free reception. Receiver operates on 12V DC through an AC Adaptor supplied alongwith the system. Each transmitter operates with a 2x1.5V AA Pencil Cell. Transmitters have 2-position ON/OFF slide switch. Audio output from receiver available at OUT 1 & OUT 2 individually and as mixed output at OUT 1 + 2. Ideal for: PA Applications... Stage & Auditoriums... Seminar Halls... Places of Worship... Recreation Centres...	Pcs	1	17,500.00	17,500.00
8	Connector & Socket	Job	1	10,000.00	10,000.00
9	Fitting and Installation	Job	1	16,000.00	16,000.00
	Total Amount (Including of GST)			**Rs.**	**2,42,100.00**
	Quoted Rate (in %)			±	
	Total Amount Quoted by the Contractor (Including of GST)			**Rs.**	

Date:

Name & Signature of the authorized signatory
(with seal of the Firm/ Company)

Annexure - 2

1) **Technical Details (to be furnished by bidder):**

1	Name of Supplier / Firm/ Company	
2	Name of the contact person with details, Mobile Numbers	
3	Full Address	
4	Telegraphic / E-mail address	
5	Telephone Numbers/ Fax No.	
6	Date of establishment of the Firm / Company	
7	GSTIN No. (Attach copy of certificate)	
8	TAN/ PAN number (Attach copy of certificate)	
9	Experience (Detail of any electrical supply/works executed in State/Central Govt. departments (attach copy of supply order) in past three years)	

Note: Document in support of all above point must be submitted as enclosure.

2) Terms & Conditions

a. Supply / Works shall be carried out as per B.O.Q./C.P.W.D. specifications.
b. All the materials required for completion of work shall conform to latest ISI/CPWD specifications.
c. All the warranty cards/ certificates of electrical items shall be provided to University for any further assistance.
d. Contractor shall not make any additional claim in rates for the variation in quantities, if any.
e. The rates quoted by the contractor include the rates for all materials, cartages, taxes etc. required for proper completion of work.
f. The authorized representative /committee of the University will accept or reject the work executed, according to the laid down norms of CPWD. The contractor is also required to modify the work suitably, as may be suggested if the work done already is not upto the proper specification.
g. In the event of any, dispute and/or differences, whatsoever arising under this order, the decision of the Vice-Chancellor, Babasaheb Bhimrao Ambedkar University shall be final and binding on the contractor.
h. The court of competent jurisdiction will be Lucknow only if any dispute arises.
i. All work executed shall be paid according to the measurements taken by or under the orders of the University and not according to the quantity given in any estimates.
j. Payment shall be released after completion of the work to the satisfaction of Engineer-in-charge.
k. The work should be completed within **45 days** from the issue of work order.
l. Income tax or any other tax shall be deducted as per Rules of Government of India/ State Government. Contractor shall be required to produce PAN number at the time of release of payment.

Certified that:

1. Terms and conditions governing this supply / works of the University is clear to me and hereby agree to abide by them.
2. The information provided by us as above regarding the details of Firms/ Company is correct and nothing has been concealed. In case any information is found to be incorrect at later stage, our bids may be summarily rejected.

Date:

Name & Signature of the authorized signatory
(with seal of the Firm/ Company)